

## **Addendum No. 1**

### **Cassia County Rodeo Grandstands Construction - 2023 project**

The following question was asked regarding the Cassia County Rodeo Grandstands Construction – 2023 project:

Detail 7 on sheet 5 of 14 calls out for 4” reinforced concrete flatwork to be placed what looks like over dirt. Normally we place all concrete flatwork over 4” of gravel subgrade. How should we price this, knowing that we should provide a subgrade but it is not called out on the drawings?

The engineer confirms that there definitely needs to be a gravel subbase. Please use the attached Revised Slab Detail in any bid submissions.